

# DEUTSCHER KALIBRIERDIENST **DKD**

Kalibrierlaboratorium für Strömungsgeschwindigkeit von Luft  
Calibration laboratory for velocity of air flow

Akkreditiert durch die / accredited by the  
Akkreditierungsstelle des Deutschen Kalibrierdienstes



**DEWI GmbH**  
Deutsches Windenergie-Institut

Deutscher  
Akkreditierungs  
Rat  
**DAkkS**  
DKD-K-28901

**Kalibrierschein**  
Calibration certificate



Kalibrierzeichen  
Calibration label

2000\_09  
DKD-K-  
28901  
08.10.09

Gegenstand Object	Cup Anemometer	Dieser Kalibrierschein dokumentiert die Rückführung auf nationale Normale zur Darstellung der Einheiten in Übereinstimmung mit dem Internationalen Einheitensystem (SI). Der DKD ist Unterzeichner der multilateralen Übereinkommen der European co-operation for Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der Kalibrierscheine. Für die Einhaltung einer angemessenen Frist zur Wiederholung der Kalibrierung ist der Benutzer verantwortlich.
Hersteller Manufacturer	Thies Clima D-37083 Göttingen	<i>This calibration certificate documents the traceability to national standards, which realize the units of measurement according to the International System of Units (SI).</i> <i>The DKD is signatory to the multilateral agreements of the European co-operation for Accreditation (EA) and of the International Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration certificates.</i> <i>The user is obliged to have the object recalibrated at appropriate intervals.</i>
Typ Type	4.3350.10.000	
Fabrikat/Serien-Nr. Serial number	body: 0909586 cup: -	
Auftraggeber Customer	EKOPOWER NL-5604 CC Eindhoven, NL	
Auftragsnummer Order No.	2000_09	
Anzahl der Seiten des Kalibrierscheines Number of pages of the certificate	3+3	
Datum der Kalibrierung Date of calibration	08.10.09	

Dieser Kalibrierschein darf nur vollständig und unverändert weiterverbreitet werden. Auszüge oder Änderungen bedürfen der Genehmigung sowohl der Akkreditierungsstelle des DKD als auch des ausstellenden Kalibrierlaboratoriums. Kalibrierscheine ohne Unterschrift und Stempel haben keine Gültigkeit.

*This calibration certificate may not be reproduced other than in full except with the permission of both the Accreditation Body of the DKD and the issuing laboratory. Calibration certificates without signature and seal are not valid.*



Stempel Seal	Datum Date	Stellv. Leiter des Kalibrierlaboratoriums Deputy head of the calibration laboratory	Bearbeiter Person in charge
	08.10.09	P. Busch Dipl.-Ing. (FH) P. Busche	R. Kluin

2000\_09

DKD-K-  
28901Kalibrierzeichen  
Calibration label

08.10.09

Kalbriergegenstand <i>Object</i>	Cup Anemometer	
Kalibrierverfahren <i>Calibration procedure</i>	MEASNET - Cup Anemometer Calibration Procedure - 9/1997 ISO 3966 – Measurement of fluid in closed conduits – 1977	
Ort der Kalibration <i>Place of calibration</i>	Windtunnel of the University of Oldenburg	
Meßbedingungen <i>Test conditions</i>		
	wind tunnel area <sup>1)</sup>	8000 cm <sup>2</sup>
	anemometer frontal area <sup>2)</sup>	315 cm <sup>2</sup>
	diameter of mounting pipe <sup>3)</sup>	34 mm
	blockage ratio <sup>4)</sup>	0.039 [-]
	blockage correction <sup>5)</sup>	0.998 [-]
	tunnel calibration <sup>6)</sup>	0.999 [-]
	average DEWI reference <sup>7)</sup>	Thies FC 0503076 : 9.80 m/s
	present DEWI reference <sup>8)</sup>	9.78 m/s
Umgebungsbedingungen <i>Ambient conditions</i>	air temperature	19.5 °C ± 1 K
	air pressure	1015.4 hPa ± 1 hPa
	relative air humidity	60.0 % ± 6 %
Dateiinformation <i>File information</i>	c:\AK\Kalibrierdaten\Doc\2009\10_2009\2000_09.doc	
Anmerkungen <i>Remarks</i>	-	
Auswertesoftware <i>Software version</i>	LV_Rev.1.6	

<sup>1)</sup> Nozzle area of the wind tunnel<sup>2)</sup> Projected cross sectional area of the anemometer<sup>3)</sup> Diameter of the mounting pipe<sup>4)</sup> Ratio <sup>2)</sup> to <sup>1)</sup><sup>5)</sup> Correction in wind speed due to the blockage effect of the anemometer<sup>6)</sup> Ratio of wind speed at the anemometer position relative to the wind speed measuring plane<sup>7)</sup> Long term average value of the reference anemometer<sup>8)</sup> Current value of the reference anemometer

2000_09
DKD-K- 28901
08.10.09

Kalibrierzeichen  
Calibration label

## Messergebnis:

Result:

Strömungs- geschwindigkeit Luft (speed of air flow)	Anzeige (anemometer signal)	Erweiterte Messunsicherheit (expanded uncertainty)* m/s
m/s	1/s	
4.030	78.599	0.10
6.046	120.244	0.10
8.053	162.071	0.10
10.170	206.376	0.10
12.187	248.532	0.10
14.225	291.770	0.10
15.808	325.340	0.11
15.292	314.546	0.10
13.224	270.706	0.10
11.218	228.779	0.10
9.138	185.231	0.10
7.104	142.513	0.10
5.040	99.600	0.10

\*) Angegeben ist die erweiterte Messunsicherheit, die sich aus der Standardmessunsicherheit durch Multiplikation mit dem Erweiterungsfaktor  $k=2$  ergibt, wobei die kleinste angebbare Messunsicherheit gemäß DKD-Akkreditierung 0.10 m/s beträgt. Die erweiterte Messunsicherheit wurde gemäß DKD-3 ermittelt. Der Wert liegt mit einer Wahrscheinlichkeit von 95% im zugeordneten Wertintervall.

Der Deutsche Kalibrierdienst ist Unterzeichner der multilateralen Übereinkommen der European co-operation for Accreditation (EA) und der International Laboratory Accreditation Cooperation (ILAC) zur gegenseitigen Anerkennung der Kalibrierscheine. Die weiteren Unterzeichner innerhalb und außerhalb Europas sind den Internetseiten von EA ([www.european-accreditation.org](http://www.european-accreditation.org)) und ILAC ([www.ilac.org](http://www.ilac.org)) zu entnehmen.

\*) The expanded uncertainty assigned to the measurement results is obtained by multiplying the standard uncertainty by the coverage factor  $k=2$ . According to the DKD-accreditation the value for the best measurement capability shall not be smaller than 0.10 m/s. The expanded uncertainty has been determined in accordance with DKD-3. The value of the measurand lies within the assigned range of values with a probability of 95%.

The DKD is signatory to the multilateral agreements of the European co-operation for Accreditation (EA) and of the International Laboratory Accreditation Cooperation (ILAC) for the mutual recognition of calibration certificates. Further signatory members within Europe and outside of Europe may be extracted from the EA-internet page ([www.european-accreditation.org](http://www.european-accreditation.org)) and the ILAC-internet page ([www.ilac.org](http://www.ilac.org))


# MEASNET Appendix

## 1. Results


DKD calibration no. 2000\_09  
 type 4.3350.10.000  
 serial number 0909586  
 cup number -  
 date 08.10.09  
 file c:\AK\Kalibrierdaten\Doc\2009\10\_2009\2000\_09.doc  
 DEWI Version LV\_Rev.1.6  
 air temperature 19.5 °C  
 air pressure 1015.4 hPa  
 air humidity 60.0 %  
 linear regression analysis  
 slope 0.04772 m ± 0.00006 m  
 offset 0.301 m/s ± 0.013 m/s  
 correlation coefficient 0.999992  
 standard error (v) 0.016 m/s  
 COV(A,B) -670.450E-9  
 remarks -



DEWI Calibration No. 2000\_09



## 2. Instrumentation



### Description of the data acquisition system

#### 1a – 4a Pitot tube

Type: Airflow (ISO 3966)  
Year: 2005  
Calibration: No; ISO 3966 [1]

#### 2b Pressure Transducer

Type: ASHCROFT XLdp  
Year: 1993  
Calibration: recalibration DEWI

#### 3b Pressure Transducer

Type: Setra 239  
Year: 2003  
Calibration: recalibration DEWI

#### 4b Pressure Transducer

Type: Setra 239  
Year: 2001  
Calibration: recalibration DEWI

#### 5 Thermometer

Type: Galtec KRC 2/5  
Serial no. 48448  
Calibration: 4706/2009/02

#### 6 Humidity Sensor

Type: Galtec KRC 2/5  
Serial no. 48448  
Calibration: 4706/2009/02

#### 7 Barometer

Type: Vaisala PTB 100A  
Serial no. U5030013  
Calibration: 05066/2009/02

#### 8 Data aquisition system

Type: NI 1042  
Year: 2003  
Calibration: checked with calibrated current, voltage and frequency standard

#### 1b Pressure Transducer

Type: ASHCROFT XLdp  
Year: 1993  
Calibration: recalibration DEWI

#### Reference Pressure transducer

Type: Ashcroft XLDP 2  
Year: 2004  
Calibration: A14742 /2009/03

#### Wind Tunnel:

University of Oldenburg

**Remark:** Ambient pressure standard is calibrated by DKD in 01/2008

Combined temperature and humidity standard is calibrated by the German 'Eichamt' in 4/2000

The multimeter is calibrated by 'DKD' in 07/2008

The frequency counter is calibrated by the German 'DKD' in 09/2007

## 3 Deviation to MEASNET Procedure

1. The time to get stable flow conditions between two speed settings is approx. 30 seconds (it has been proven for this tunnel that 30 seconds are sufficient enough to establish a stable flow).
2. The expanded uncertainty from page 3 shows only values  $\geq 0.10$  m/s due to the *best measurement capability* of 0.10 m/s as defined by the DKD accreditation.




Photo showing the anemometer and the mounting system in the wind tunnel.  
The anemometer shown in the photo is not the actual calibrated one but it is identical with the calibrated anemometer.  
Remark: The photo does not show the real proportions, it is distorted by the lens of the camera.

#### 4 References

- [1] MEASNET  
Cup Anemometer Calibration Procedure  
September 1997
- [2] ISO 3966 1977  
Measurement of fluid flow in closed conduits.
- [3] H.Klug, P.Busche, K.Nolopp 2005  
DEWI QMH-AKL Rev.05